OUR TOWN HALL PROJECT

Document Name: Canopy-04 Schedule

Document Ref: OTH-HAK-TH-01-SCH-V-0005

Status: S4 – Suitable for Construction

Document Type: Schedules

Revision History:

REV.	DATE	DESCRIPTION OF CHANGE
P01	23/08/2019	Issue For Comment
P02	30/08/2019	Issue For Tender
P03	21/02/2023	Issued For Construction

Not Confidential - Internal

Canopy-04 Schedule

Project :	**Manchester Town Hall Catering Works**	Project No :	**50801**	Schedule Ref :	**OTH-HAK-TH-01-SCH-V-0005**
		Area Served :	**Level 01**	Purpose of Issue :	**Suitable for Construction**
		Issue Date :	**21 February 2023**	Revision :	**P03**

Canopy-04 Details		
Manufacturer		Halton or Equal and Approved
Model		CXW
Quanity		1
Reference		Canopy-04
Canopy Size	(mm)	1800 x 1250 x 555
Extract Flowrate	(m^3/s)	0.45
Static Pressure at Extract Spigot	Pa	40
Extract Spigots (20 Mez)	(mm)	1No. 300 x 300
Approx Hanging Weight	kg	113

General Specification

- Canopy-04 Shall be Complete With 1No. 300x300 Aluminium Egg-Grate Grille (Removable Core) With Opposed-Blade Damper.

Revision	Revision Notes	Revision Date
P01	Tender - For Comment	23 August 2019
P02	Issue For Tender	30 August 2019
P03	Suitable for Construction	21 February 2023