OUR TOWN HALL PROJECT

Document Name: Drainage Pump Schedule

Document Ref: OTH-HAK-TH-01-SCH-V-0014

Status: S4 – Suitable for Construction

Document Type: Schedules

Revision History:

REV.	DATE	DESCRIPTION OF CHANGE
C01	08/11/2023	Issued for Construction

Drainage Pump Schedule

Project :	**Manchester Town Hall Catering Works**	Project No :	**50801**	Schedule Ref :	**OTH-HAK-TH-01-SCH-V-0014**
		Area Served :	**Catering Kitchen**	Purpose of Issue :	**Suitable for Construction**
		Issue Date :	**08 November 2023**	Revision :	**C01**

Pump Details		
Manufacturer		Environmental Products and Services Ltd or Equal and Approved
Model		CombiPump
Quanity		1
Pump References		P-01
Max. Flow		2 l/s
Max. Head		6.5 m
Inlet/Outlet		x2 50mm in, x2 out (32mm & 50mm Emergency)
Power Supply		230 VAC, 1.3A, 50/60Hz

General Specification

- Key Features:

  Automatic Float Switch Activation

  Low Level Inlet Position

Revision	Revision Notes	Revision Date
C01	Issued for Construction	08 November 2023