OUR TOWN HALL PROJECT

Document Name: Enzyme De-Greaser Schedule

Document Ref: OTH-HAK-TH-01-SCH-V-0008

Status: S4 – Suitable for Construction

Document Type: Schedules

Revision History:

REV.	DATE	DESCRIPTION OF CHANGE
P01	23/08/2019	Issue For Comment
P02	30/08/2019	Issue For Tender
P03	21/02/2023	Issued For Construction

Enzyme De-Greaser Schedule

Project :	**Manchester Town Hall Catering Works**	Project No :	**50801**	Schedule Ref :	**OTH-HAK-TH-01-SCH-V-0008**
		Area Served :	**Level 01**	Purpose of Issue :	**Suitable for Construction**
		Issue Date :	**21 February 2023**	Revision :	**P03**

De-Greaser Details		
Manufacturer		Hydra Bio or Equal and Approved
Model		Hydra Battery Operated Auto Dosing Unit Complete Includes 20L Hydra Grease-Eater Liquid
Quanity		1
Reference		DE-01
Capacity		20L

General Specification

- The De-Greaser is a Grease Trap Treatment Including Hydra Auto Dosing Timer Pump and Enzyme Enhanced Cleaning Liquid For Grease Removal.
- Automatically Adds Grease-Eater Liquid Solution Direct to The Problem Area.
- 12 Months Warranty
- Final De-Greaser Selection to be Confirmed With The Client Prior to Procurement and Installation.

Revision	Revision Notes	Revision Date
P01	Tender - For Comment	23 August 2019
P02	Issue For Tender	30 August 2019
P03	Suitable for Construction	21 February 2023