Extract Grille Schedule

Project :	**Manchester Town Hall Catering Works**	Project No :	**50801**	Schedule Ref :	**OTH-HAK-TH-ZZ-SCH-V-0002**
		Area Served :	**Catering Areas**	Purpose of Issue :	**Issued for Construction**
		Issue Date :	**03 September 2025**	Revision :	**C02**

Diffuser Reference	Area Served	Air Volume (litres/second)	Overall Size (mm x mm)	Neck Size (mm x mm)	Spigot Diameter (mm)	Plenum Type (Side/Top Entry)	Plenum Box Dimensions			Diffuser Type	Diffuser Colour	Maximum Noise Level	Maximum P.D (Pa)
							Width (mm)	Depth (mm)	Height (mm)				
EX-01	GF-032	100	599x599	527x527	250	Top Entry	-	-	-	Gilberts GECAB-RC	TBC by Architect	40 NC	<10
EX-02	GF-031	106	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC	TBC by Architect	25 NC	<10
EX-03	GF-031	600	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC	TBC by Architect	40 NC	<10
EX-04	GF-031	600	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC	TBC by Architect	40 NC	<10
EX-05	GF-031	600	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC	TBC by Architect	40 NC	<10
EX-06	GF-003	360	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC	TBC by Architect	25 NC	<10
EX-07	01-039	540	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC	TBC by Architect	40 NC	<10
EX-08	01-039	496	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site					Gilberts GECAB-RC, DO	TBC by Architect	40 NC	<10
EX-09	01-039	1000	1199x599	1127x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC, DO	TBC by Architect	32 NC	<10
EX-10	01-007	197	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC	TBC by Architect	25 NC	<10
EX-11	01-007	197	599x599	527x527	Direct connection to grille/ Contractor to fabricate connection on site		-	-	-	Gilberts GECAB-RC	TBC by Architect	25 NC	<10

Note: The Contractor shall allow for all extract grilles to be constructed from Aluminium.

Note: The Contractor shall confirm ceiling/wall type for all extract grilles prior to procurement and finalise grille schedules, as necessary, in conjunction with the respective manufacturer.

Note: The Contractor shall allow for all extract grilles to have removable cores.

Note: The Contractor shall allow for all extract grilles to be fitted with blanking plates suitable to each extract grilles neck size.

Note: Final Plenum Box sizes to be as per manufacturers requirements.

Revision	Revision Notes	Revision Date
P01	Tender - For Comment	23 August 2019
P02	Issue For Tender	30 August 2019
P03	Suitable for Construction	21 February 2023
C01	Issued for Construction	02 February 2024
C02	Issued for Construction	03 September 2025