

PLANTING SCHEDULE

TREES

Qty	Code	Name	Girth	Height cm	Specification
22	AcE	Acer campestre 'Elegant'	12-14	400-450	RB 3x; Standard; clear stem minimum 200cm; 3 breaks
9	Ab	Amelanchier 'Ballerina'	12-14	400-450	RB 3x; Standard; clear stem minimum 200cm; 3 breaks

HEDGES

Length (Lin M)	No. Of Plants	**Code**/Species	Size in cm	Root / Pot size	Density	Specification
127	635	**H1 /** Carpinus betulus	40-60	3L Pot	5 / Lin m	Branched; 6 breaks
132	660	**H2** / Fagus sylvatica 'Purpurea'	60-80	3L Pot	5 / Lin m	Bushy; 5 breaks

WILDFLOWER AND GRASSLAND PLANTING

Code	Area (m2)	Seed Mix Specification	Specification
WFM1	257	Emorsgate EM3 Wildflower Mixture	Suppliers recommendations - sowing rate 4g/m2. Gardens to be turfed and POS seeded / overseeded as required
RG1	66	Rain Garden Mix	RP11 Swales, Pond & Bankside Grass Seed Mix - Supplied by Hurrells. Sowing Rate 4g/m2

Note: Wildflower mix to be overseeded in areas of existing grassland and under RPA where no dig method required

SHRUBS

Shrub bed composition to be laid out and agreed with Landscape Architect prior to planting

Qty	Abbrev.	Name	Rate / m2	Height	Container Size	Specification
39	ABE GRA	Abelia grandiflora	3	30-40	3L	Bushy; 3 breaks
67	CHO TER	Choisya ternata	3	30-40	3L	Bushy; 4 breaks
39	ELE EBB	Eleagnus x ebbingei	3	30-40	3L	Bushy; 4 breaks
66	EUO GAI	Euonymus fortunii 'Gaiety'	3	30-40	3L	Bushy; 4 breaks
48	HEB ORM	Hebe 'Great Orme'	3	30-40	3L	Bushy; 5 breaks
86	HEB RAK	Hebe rakaiensis	3	20-30D	3L	Bushy; 5 breaks
151	PAC TER	Pachysandra Terminalis	7	20-30D	2L	Bushy; 5 breaks
58	PHO ROB	Photinia 'Red Robin'	3	30-40	3L	Bushy; 5 breaks
37	SKI KEW	Skimmia x confusa 'Kew Green'	5	30-40	3L	Bushy; 3 breaks
41	VIB DAV	Viburnum davidii	5	20-30	3L	Bushy; 3 brks

LEGEND

SITE BOUNDARY

EXISTING RETAINED VEGETATION
Refer to the Arboricultural Report for further details on species and condition and recommendations. Refer to tree survey for details on TPOs

ROOT PROTECTION AREA
Refer to the Arboricultural Report for further details on species and condition and recommendations. Where planting falls within the RPA, hand dig trenches / pits to be used (machine excavation is inappropriate)

PROPOSED TREES
Refer to the planting schedule for further details on species, quantities and nursery specification.

SHRUBS
Please refer to the planting schedule for further details on species, quantities and nursery specification.

HEDGEROWS
Please refer to the planting schedule for further details on species, quantities and nursery specification.

GRASS
Front gardens to be laid to turf. Areas of amenity grass to be either turfed, seeded or overseeded.

RAIN GARDENS
Hurrells Seed Mix - See Schedule 66m²

GRAVEL / SLATE MULCH
In narrow areas between drives etc

WILDFLOWER PLANTING
Please refer to the planting schedule for further details on species, quantities and nursery specification. Where wildflower is within the RPA overseeding to be required 257 m²

REAR GARDENS
To be turfed

Rev	Date	Description	Initials
P2	13.08.26	Add tree	PGG
P1	11.08.26	Initial Issue	PGG

pgla | landscape architects

PGLA Ltd
Landscape Architects
Station Hop Offices
815 Stockport Road
Manchester
M19 3BS

t: 0161 238 9138
e: info@pgla.co.uk
w: www.pgla.co.uk

Client
VIEWS

Project
FORMER BURNAGE CRICKET CLUB

Description
PLANTING PLAN AND SCHEDULE

STAGE 03 - UPDATE

Status
FOR PLANNING

Scale	Drawn	Checked	Date
1:250@A1	KLJ	PGG	AUG 2026

Job number	Drawing number	Revision
BUR2604	PP01.01	P2

Original size 100mm @ A1