

2 Rear Proposed
1 : 100



1 Rear Extisting
1 : 100

RL	Rooflight
ESS	Replace existing windows with UPVC thin section top and side hung
SS	New UPVC thin section sliding sash window
TT	Replace existing windows with UPVC thin section Tilt and Turn window
TH	New UPVC top hung window
PD	Traditional black painted timber door to match original / adjacent front doors
JB	Glass Juliet Balcony
UD	UPVC door
NP	New traditional porch roof over new main entrance
ZSS	Zinc standing seam cladding. Natural finish.
BMB	Black painted metal balustrade railing - 1.1m tall (BMB)
CRB	Clean and repoint brickwork
RR	Refurbish existing slate roof. Replace broken slate.

project
105 - 111 Egerton Road

client name
STANTON

Contract No.	SIE	PHASE	drawing number	rev
XXX	105	PL	EL03	A

drawing
Rear Elevation

Stage Code
PLANNING

Date	Rev
17/08/26	A

scale
1 : 100

Sheet
A3

Martin Degnen & James
96 Marbury Road, SK4 5NG
07795323381