

KEY

Hard Works

- **Vehicular Asphalt Surfacing** — To roads. Black colour. *To engineer specification & recommendation*
- **Pedestrian Asphalt Surfacing** — To pavements. Black colour. *To engineer specification & recommendation*
- **Vehicular Asphalt Surfacing with Red Chip** — To feature junctions. Black with Hard light grey chip. *To engineer specification & recommendation*
- **Precast Concrete Flag Paving** — To private paths and patios.
- **Reclaimed Sett Paving** — To pedestrian thresholds. Reclaimed from site.
- **Precast Concrete Block Paving** — To vehicular thresholds, Tobermore City Pave. Colours: Silver / Mid Grey Mix.
- **Self Binding Gravel Surfacing** — To pathways. Buff colour.
- **Tactile paving** — To crossing points as per highways engineer details.
- **1.8m Brick Pier With Brick Panel** — 1800mm high, with engineering brick to cap. Brick to match architecture.
- **1.0m Metal Railings with Kerb Upstand** — 1000mm high
- **1.0m Metal Railings on Low Wall** — 1000mm high. With matching gates.
- **1.8m Timber Feather Edge Fence** — 1800mm high, adjacent to public space 2100mm high with 300mm timber trellis structure.With matching gates.
- **2.4m V-Mesh Fencing** — Green Colour
- **2.4m V-Mesh Combined with Timber Slats** — Green Colour
- **2.1m Acoustic Fencing**
- **Picnic Benches** — Fordham Picnic Bench - Furnitubes or equal and approved.
- **Benches** — Fordham Bench - Furnitubes or equal and approved.
- **Timber Play Features**
- **Play Boulders**
- **Installations** — *Opportunity to salvage industrial artefacts from site.*
- **Bollards** — *Opportunity to salvage industrial artefacts from site.*
- **Bat Boxes** — Proposed locations TBC as per ecologists proposals
- **Bird Brick** — Proposed locations TBC as per ecologists proposals
- **Swift Brick** — To ecologists proposals
- **Hedgehog Highway Fence Openings** — To ecologists proposals

Soft Works

- **Existing Vegetation** — To be retained and enhanced
- **Proposed Feature Tree Planting** — Heavy standard.
- **Proposed Standard Tree Planting** — Standard.
- **Proposed Feature Shrub Planting**
- **Proposed Climbing Plants**
- **Proposed Ornamental Hedge Planting** — Single species ornamental shrubs - see schedule for species
- **Proposed Native Hedge Planting** — Native hedgerow mix - See schedule for species
- **Proposed Ornamental Shrub Planting** — Shrub mix - See schedule for species
- **Proposed Native Shrub Planting** — Native shrub mix - See schedule for species
- **Proposed Feature Mixed Planting 1** — Herbaceous, grass & shrub species mix. Herbaceous mix 1- See schedule for species
- **Proposed Feature Mixed Planting 2** — Herbaceous, grass & shrub species mix. Herbaceous mix 2- See schedule for species
- **Proposed Groundcover Planting** — Ornamental groundcover mix- See schedule for species
- **Proposed Wildflower Meadow** — Urban Polinator Mix- See schedule for species
- **SUDs Planting mix** — Refer to planting schedule
- **Proposed Turf Grass** — To amenity spaces and front gardens.
- **Proposed Seeded Amenity Grass** — To rear gardens.

Do not scale this drawing (printed or electronic version).

Contractors must check all dimensions from site

This drawing is copyright and is for use on this site only. This drawing should be read in conjunction with all relevant consultants drawings and specialist subcontractors / supply chain drawings and specifications.

All works to be carried out in accordance with the latest British Standards / Codes of Practice unless specifically directed otherwise in the specification.

Responsibility for the reproduction of this drawing in paper form, or issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when comparedto the original paper or electronic image.

Graphical representations of equipment on this drawing have been co-ordinated, but are approximations only. Please refer to the specifications and / or details for actual sizes and / or specific contractor construction information.

Notes:-

REV.	DATE	DESCRIPTION	DRAWN	CHK'D
P25	11/08/26	LPA Comments	GBS	SA
P24	21/07/26	Canal 15m offset added	GBS	SA
P23	27/04/26	UPDATE	JW	SA
P22	15/04/26	UPDATE	JW	SA
P21	17/02/26	UPDATE	AL	SA
P20	12/01/26	UPDATE	TH	SA
P19	12/01/26	UPDATE	TH	SA
P18	03/12/25	UPDATE	AG	GBS
P17	31/07/25	MINOR UPDATE	GBS	SA
P16	16/07/25	MINOR UPDATE	GBS	SA
P15	07/07/25	UPDATE	GBS	SA
P14	11/04/25	UPDATE	IG	AL
P13	08/04/25	UPDATE	IG	AL
P12	04/04/25	UPDATE	AL	SA
P11	03/04/25	UPDATE	AL	SA
P10	31/03/25	UPDATE	AL	SA
P09	28/03/25	UPDATE	AL	SA
P08	25/02/25	UPDATE	AL	SA
P07	21/02/25	UPDATE	AL	SA
P06	07/02/25	UPDATE	MA	SA
P05	16/01/25	UPDATE	MA	AL
P04	08/01/25	UPDATE	MA	SA
P03	20/12/24	UPDATE	MA	SA
P02	13/12/24	UPDATE	IG	SA
P01	22/11/24	FIRST ISSUE	IG	SA

URBAN GREEN

A: Ground Floor, The Tower, Deva City Office Park, Trinity Way, Manchester M3 7BF

T: +44 (0) 161 312 3131

weareurbangreen.co.uk

Client:
KEEPMOAT HOMES

Project:
THE IRONWORKS LAND AT CRABTREE LANE

Title:
GENERAL ARRANGEMENT

Issue:
PLANNING

Drawn:	Checked:	Approved:
IG	AL	SA
Project: UG2791	**Scale @ A1:** 1:500	**Date:** 22/11/24
Dwg No: UG_2791_LAN_GA_DRW_101		**Revision:** P25