

RWP 82

**Princess Street courtyard
Repairs behind rainwater
pipes at mosaic locations**

Lift 6

Replacement mosaic tiles
matching original as NBS
specification reference C41.278

Replacement tiles to be re-fixed
and grouted using Sencil Tek
Adhere Cal NHL fixing mortar

Replace missing render immediately behind
rainwater pipe
Mix: 1 part NHL lime : 2 parts aggregate
Lime: St Astier NHL 3.5
Aggregate: Washed Sharp sand
Reinforcement: Bellmix flock polypropylene
fibres 18mm - 500g to 2 kg per tonne

Fill hole
Mix: 1 part NHL lime : 2 parts aggregate
Lime: St Astier NHL 3.5
Aggregate: Washed Sharp sand
Reinforcement: Bellmix flock polypropylene
fibres 18mm - 500g to 2 kg per tonne

Page 1 of 7

Revision: -
First issue
Date: 24.07.2024

OTH-PUR-TH-RF-SKE-A- 3750

RWP 82

**Princess Street courtyard
Repairs behind rainwater
pipes at mosaic locations**

Lift 5 Overview

Top

Bottom

Page 2 of 7

Revision: -

First issue

Date: 24.07.2024

OTH-PUR-TH-RF-SKE-A- 3750

RWP 82

Princess Street courtyard Repairs behind rainwater pipes at mosaic locations

Lift 5 Top

Replacement mosaic tiles
matching original as NBS
specification reference C41.278

Replacement tiles to be re-fixed
and grouted using Sencil Tek
Adhere Cal NHL fixing mortar

Carefully remove oak plug,
remove loose or de-bonded
mosaic and fit new plug before
replacing missing tiles

Fill hole
Mix: 1 part NHL lime : 2 parts aggregate
Lime: St Astier NHL 3.5
Aggregate: Washed Sharp sand
Reinforcement: Bellmix flock polypropylene
fibres 18mm - 500g to 2 kg per tonne

Replace missing render immediately behind
rainwater pipe
Mix: 1 part NHL lime : 2 parts aggregate
Lime: St Astier NHL 3.5
Aggregate: Washed Sharp sand
Reinforcement: Bellmix flock polypropylene
fibres 18mm - 500g to 2 kg per tonne

Page 3 of 7

Revision: -
First issue
Date: 24.07.2024

OTH-PUR-TH-RF-SKE-A- 3750

RWP 82

**Princess Street courtyard
Repairs behind rainwater
pipes at mosaic locations**

Lift 5 Bottom

Fill hole
Mix: 1 part NHL lime : 2 parts aggregate
Lime: St Astier NHL 3.5
Aggregate: Washed Sharp sand
Reinforcement: Bellmix flock
polypropylene fibres 18mm - 500g to 2 kg
per tonne

Replacement tiles to be re-fixed
and grouted using Sencil Tek
Adhere Cal NHL fixing mortar

Replacement mosaic tiles
matching original as NBS
specification reference C41.278

Replace missing render immediately behind
rainwater pipe
Mix: 1 part NHL lime : 2 parts aggregate
Lime: St Astier NHL 3.5
Aggregate: Washed Sharp sand
Reinforcement: Bellmix flock polypropylene
fibres 18mm - 500g to 2 kg per tonne

Page 4 of 7

Revision: -
First issue
Date: 24.07.2024

OTH-PUR-TH-RF-SKE-A- 3750

RWP 82

**Princess Street courtyard
Repairs behind rainwater
pipes at mosaic locations**

Lift 3 Overview

Top

Bottom

Page 5 of 7

**Revision: -
First issue**

Date: 24.07.2024

OTH-PUR-TH-RF-SKE-A- 3750

OTH-PUR-TH-RF-SKE-A- 3750

RWP 82

**Princess Street courtyard
Repairs behind rainwater
pipes at mosaic locations**

Lift 3 Top

Carefully remove oak plug,
remove loose or de-bonded
mosaic and fit new plug before
replacing missing tiles

Replace missing render immediately behind
rainwater pipe

Mix: 1 part NHL lime : 2 parts aggregate

Lime: St Astier NHL 3.5

Aggregate: Washed Sharp sand

Reinforcement: Bellmix flock polypropylene
fibres 18mm - 500g to 2 kg per tonne

Replacement tiles to be re-fixed
and grouted using Sencil Tek
Adhere Cal NHL fixing mortar

Replacement mosaic tiles
matching original as NBS
specification reference C41.278

Page 6 of 7

Revision: -

First issue

Date: 24.07.2024

OTH-PUR-TH-RF-SKE-A- 3750

RWP 82

**Princess Street courtyard
Repairs behind rainwater
pipes at mosaic locations**

Lift 3 Bottom

Replacement mosaic tiles
matching original as NBS
specification reference C41.278

Replace missing render immediately behind
rainwater pipe
Mix: 1 part NHL lime : 2 parts aggregate
Lime: St Astier NHL 3.5
Aggregate: Washed Sharp sand
Reinforcement: Bellmix flock polypropylene
fibres 18mm - 500g to 2 kg per tonne

Carefully remove oak plug,
remove loose or de-bonded
mosaic and fit new plug before
replacing missing tiles

Replacement tiles to be re-fixed
and grouted using Sencil Tek
Adhere Cal NHL fixing mortar

Fill hole
Mix: 1 part NHL lime : 2 parts aggregate
Lime: St Astier NHL 3.5
Aggregate: Washed Sharp sand
Reinforcement: Bellmix flock
polypropylene fibres 18mm - 500g to 2 kg
per tonne

Page 7 of 7

Revision: -
First issue
Date: 24.07.2024