

**Roof WR19 Albert Square/
Lloyd Street plant area
Holes through brick wall
for services from riser 1 to
roof top plant**

Core hole diameters

- 1 - VRF 75mm diameter
- 2 - VRF 60mm diameter
- 3 - VRF 55mm diameter
- 4 - DX 55mm diameter
- 5 - DX 55mm diameter
- 6 - Cable 50mm diameter
- 7 - Cable 50mm diameter
- 8 - Cable 50mm diameter
- 9 - Cable 50mm diameter

All holes are to be core drilled through the middle of the header bricks shown ensuring equal margins between top and bottom and each side

Assumed rafter/ceiling line to be checked when access is available before proceeding

Drill 10mm diameter pilot hole through middle of brick 2 to allow Purcell to check the location of all the other holes internally before proceeding with any other work

Revision: -
First issue
Date: 30 October 2024

OTH-PUR-TH-RF-SKE-A-3855