A0

Cabinet with 2 x Plastic Water pipes.

Unable to find position of Gas line with GPR.

MH CL=64.37 IL=64.02

MH CL=64.24 IL=63.37

MH CL=64.35 IL=62.23

MH CL=64.32 IL=63.63

MH CL=63.98 IL=62.09

MH CL=63.89 IL=62.39 Top of Pipe

Unable to get line down drain to trace.

Downpipe enclosed unable to place line down to trace, GPR results inconclusive.

Downpipe enclosed unable to place line down to trace, GPR results inconclusive.

Unable to get line in to trace, MH requires jetting. Inconclusive results with GPR

Canopy Level - 66.87m

Canopy Level - 67.39m

Canopy Level - 66.87m

Security Fence

Security Fence

Concrete Edge Channel

Tarmac

Grass

Gas

GY

Dp

PO

H

Poor Signal

394820N

394810N

394800N

394790N

This drawing is copyright and remains the property of Black Cat Building Consultancy.

All drawings are to be read in conjunction with all accompanying information. All dimensions must be checked and verified on site before commencing any work or producing drawings.

Any discrepancy's found should be imediately notified to Black Cat Building Consultancy.

Once drawing is in general circulation Black Cat Building Consultancy take no responsibility for the accuracy or information taken from them.

| Rev | Description | Dr By | Ap By | Date |
|---|---|---|---|---|
| A | Revised for tender | RB | AMcG | 03.07.2026 |

CLIENT NAME
Bright Futures Educational Trust

CONTRACT/PROJECT NAME
Gorton Education Village
Dining Hall Extension

DRAWING TITLE
Existing Landscape Plan

| PROJECT NUMBER | DATE |
|---|---|
| | 23.06.2026 |
| DRAWING NUMBER | REVISION |
| BFET-GEV-DHE-L-P-00-001 | A |
| SCALE | DRAWN BY |
| 1:50 @A0 | RB |
| ISSUE STATUS | APPROVED BY |
| Tender | AMcG |

BLACK CAT HQ
ONE ST JAMES SQUARE
MANCHESTER
M2 6DN
+44 (0) 161 359 4313
enquiries@bcconsultancy.co.uk

BLACK CAT

0 0.5 1 1.5 2 2.5m
Scale - 1:50