

PLANTING SCHEDULE

Client: **Manchester University**
Location: **Manchester**
Drawing ref: **440-LYR-XX-ZZ-SCH-L-0000 Planting Schedule**
Revision: **01**
Notes: **General densities shown - plant quantities subject to detailed planting plans**

Date: 11-08-26

Manchester
Bb Grove Street
Wilmslow
Cheshire
SK9 1DR
0161 523 157
manchester@layer.studio

Newcastle
Studio 29
39 High Bridge Works
Newcastle-upon-Tyne
NE1 1EW
www.layer.studio
newcastle@layer.studio

Layer.studio

Clear-Stem Trees								
Abbrev.	Botanical Name	Common Name	Girth/ Dia. cm	Height cm	Root Zone	Specification		Quantity
A ca 'El'	Acer campestre 'Elsrijk'		10-12	300-350	RB	3X; EHS; clear stem min. 200cm		As Shown
Al	Amelanchier lamarckii			350-400	RB	Multi-stem; bushy; 5 stems min.		As Shown
Buj	Betula Utilis jacquemontii			350-400	RB	Multi-stem; bushy; 5 stems min.		As Shown
Cbe	Carpinus betulus		10-12	300-350	RB	2x; SS; clear stem 175-200cm; 4 brks		As Shown
Pav	Prunus Avium		10-12	300-350	RB	2x; SS; clear stem 175-200cm; 4 brks		As Shown

Biodiverse Shrubs and Grasses Mix 1. -							Total m2	32
Abbrev.	Botanical Name	Common Name	Girth/ Dia. cm	Height cm	Root Zone	Specification	Density m2	% mix
Dc 'G'	Deschampsia cespitosa 'Goldtau'		/	/	P9	Full pot	7	20.0%
St 'P'	Stipa tenuissima 'Pony Tails'		/	/	P9	Full pot	7	15.0%
Vb	Verbena bonariensis		/	/	P9	Full pot	13	15.0%
Ek	Erigeron karvinskianus		/	/	P9	Full pot	9	5.0%
G n	Lavandula angustifolia		/	/	P9	Full pot	13	10.0%
Sa	Scabiosa astropurpurea 'Black Knight'		/	/	P9	Full pot	5	5.0%
H	Hylotelephium 'Herbstfreude'		/	/	P9	Full pot	5	5.0%
H 'mb'	Helenium 'Moerheim Beauty'		/	/	P9	Full pot	7	10.0%
R	Rudbekia 'Goldstrum'		/	/	P9	Full pot	9	5.0%
E pu	Echinacea purpurea		/	/	P9	Full pot	7	5.0%
A sc	Allium schoenoprasum		/	/	P9	Full pot	9	5.0%
			/	/				

Wildflower Mix - 140m2			Total Area	140m2
Reference	Wildflower/ Grass mixes	Sowing Rate	Supplier	
LW7M	Hedgerow and Light Shade Wildflower and Grass Seeds LW7M 80/20	5g per sq/m	https://www.wildflower.co.uk/products/lw7-hedgerow-light-shade-80-20.html	

NOTES:
1. DO NOT SCALE FROM THIS DRAWING. ALWAYS WORK TO NOTED DIMENSIONS.
2. ALL SETTING OUT, LEVELS AND DIMENSIONS TO BE CHECKED ON SITE PRIOR TO THE INSTALLATION OF MATERIALS AND ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
3. THIS DRAWING MUST BE READ WITH THE RELEVANT SPECIFICATION DOCUMENTS AND DETAIL DRAWINGS. ANY DISCREPANCIES MUST BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
4. THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY.
5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
6. NOTE DRAWING SUITABILITY CODE SHOWN BELOW. DRAWING NOT TO BE USED FOR CONTRACTUAL AGREEMENT WITHOUT A1 STATUS.

THIS DRAWING WAS PLOTTED ON:
20/08/2026

REVISION HISTORY

DATE	REV	ZONE	DESCRIPTION	CHK
22/07/2026	P02		Stage 2 Issue	OK
11/08/2026	P03		Stage 2 update	OK
20/08/2026	P04		Fence Update	OK

KEY

GENERAL INFORMATION

APPLICATION SITE BOUNDARY

SOFTWORKS

CLEAR-STEM/ MULTI STEM TREE PLANTING
Refer to Planting Schedule

ORNAMENTAL SHRUBS AND GRASSES MIX 1
To Building Elevation
Subject to Future Detail

WILDFLOWER SEEDING
To Edges
Subject to Future Detail

ORIGINATOR
Layer.studio
MANCHESTER NEWCASTLE BRISTOL
W layer.studio T 01625 523 157 E manchester, newcastle or bristol@layer.studio

Client: **UoM**
Project: **The Limes**
Manchester
Drawing Title: **Softworks**

Created By	Checked By	Scale	Sheet Size
OK	ST	1:250@A1	A1

Project Number	Originator	Volume	Level	File Type	Discipline	Number
440	LYR	XX-ZZ-DWG-L-3001				

Work Stage	Status	Revision
Stage 2	A1 Stage 2 Issue	P04