Heater in LG-012 to be located under reinstated shelving.

Some piepwork will pass through shelving. For reinstatement/adaptations required to joinery, see joinery schedule OTH-PUR-TH-ZZ-SCH-A-5890 and FFE Package

Type 10 perimeter boxing omitted to these areas as heating is now electric so hearting pipework is no longer needed.

Pipework within Services route to be highlevel. No perimeter boxing required

Type 10 perimeter boxing omitted to these areas as heating is now electric so hearting pipework is no longer needed.

Pipework within Services route to be highlevel. No perimeter boxing required

Heaters mounted to walls at side of door

Fin tube heaters mounted at high level on crash deck

Arup1-EWN-000083

Fin tube heaters mounted at high level on crash deck

No heating in LG-036a Pipework for neighbouring rooms to be routed to ventilation kit

Type 01 - FCU - OTH-PUR-TH-ZZ-DWG-A-5920
Type 02 - Finned Tube - OTH-PUR-TH-ZZ-DWG-A-5921
Type 03 - Level 06, boxing wihin Eaves - OTH-PUR-TH-ZZ-DWG-A-5922
Type 04 - Welfare - OTH-PUR-TH-ZZ-DWG-A-5923
Type 05 - Box-in-Box Kitchen - OTH-PUR-TH-ZZ-DWG-A-5924
Type 06 - ZE Box
Type 07 - Heritage Boxing to be altered - See references on layouts
Type 08 - Heritage Rooms - Services below FFL with trench heaters
Type 09 - Storage Rooms - Unistrut framing only
Type 10 - Heating Pipes fixed on floor or wall - WPC to submit design for services fixing methodology. May wish to continue using unistrut module.
Type 11 - Slimline version of type 1 FCU boxing. See OTH-PUR-TH-GF-DWG-5989 for details.
Type 12 - Boxing to dormer windows on Level 05. See OTH-PUR-TH-05-DWG-A-6410 for details.
Type 13 - Low level skirting boxing detail to suit existing skirting profile type. See OTH-PUR-TH-03-DWG-A-5996 for details.
Type 13a For existing 375mm high skirting
Type 13b For existing 220mm high skirting
Type 14 - Boxing principles based on type 2, but no finned tubes are present and radiators are face-fixed to boxing. See OTH-PUR-TH-ZZ-DWG-A-5327 for details.
Type 15 -Replica Heritage Boxing - OTH-PUR-TH-06-DWG-A-5829
Special - Area of boxings that vary from the standard type. See relevant setting out drawings for details.

Cabintnetry Location - Lower Ground

1 : 200

Scale Bars to be used as guidance only - refer to sheet size below

1:100	mm	1000		3000		5000		7000
1:200	mm	5000		8000		12000		16000
1:500	M	5		15		25		35
1:1250	M	10		30		50	70	90

Notes:
Drawings are based on survey data and may not accurately represent what is physically present.
Do not scale from this drawing. All dimensions are to be verified on site before proceeding with the work.
All dimensions are in millimeters unless noted otherwise.
Purcell shall be notified in writing of any discrepancies.

Key Plan

To be read in conjunction with New Perimeter Boxing Type Details:
- OTH-PUR-TH-ZZ-DWG-A-5920
- OTH-PUR-TH-ZZ-DWG-A-5921
- OTH-PUR-TH-ZZ-DWG-A-5922
- OTH-PUR-TH-ZZ-DWG-A-5923
- OTH-PUR-TH-ZZ-DWG-A-5924

and Schedule:
- OTH-PUR-TH-ZZ-SCH-A-5919

These drawings illustrate the locations of boxing types and are not to be used to calculate the dimensions of perimeter boxings. They are based on ARUP schedule:
- OTH-ARU-TH-ZZ-SCH-A-0011

To be read in conjuction with New Perimeter Boxing Setting Out:
- OTH-PUR-TH-ZZ-DWG-A-5989
- OTH-PUR-TH-ZZ-DWG-A-5990
- OTH-PUR-TH-ZZ-DWG-A-5991
- OTH-PUR-TH-ZZ-DWG-A-5992
- OTH-PUR-TH-ZZ-DWG-A-5993
- OTH-PUR-TH-ZZ-DWG-A-5994
- OTH-PUR-TH-ZZ-DWG-A-5995
- OTH-PUR-TH-ZZ-DWG-A-5996 (includes type 13a and b details)
- OTH-PUR-TH-ZZ-DWG-A-5997
- OTH-PUR-TH-ZZ-DWG-A-5998
- OTH-PUR-TH-ZZ-DWG-A-5999
- OTH-PUR-TH-03-DWG-5326

For Services below FFL with Trench Heaters refer to:
- OTH-PUR-TH-ZZ-DWG-A-0620
- OTH-PUR-TH-ZZ-DWG-A-0621

To be read in conjunction with Heritage Boxing Alteration Details:
- OTH-PUR-TH-ZZ-DWG-A-5950
- OTH-PUR-TH-ZZ-DWG-A-5951
- OTH-PUR-TH-ZZ-DWG-A-5952
- OTH-PUR-TH-ZZ-DWG-A-5953
- OTH-PUR-TH-ZZ-DWG-A-5954
- OTH-PUR-TH-ZZ-DWG-A-5955
- OTH-PUR-TH-ZZ-DWG-A-5956
- OTH-PUR-TH-ZZ-DWG-A-5957
- OTH-PUR-TH-ZZ-DWG-A-5958
- OTH-PUR-TH-ZZ-DWG-A-5960
- OTH-PUR-TH-ZZ-DWG-A-5961
- OTH-PUR-TH-ZZ-DWG-A-5962
- OTH-PUR-TH-ZZ-DWG-A-5963
- OTH-PUR-TH-ZZ-DWG-A-5964
- OTH-PUR-TH-ZZ-DWG-A-5966
- OTH-PUR-TH-ZZ-DWG-A-5967
- OTH-PUR-TH-ZZ-DWG-A-5968
- OTH-PUR-TH-ZZ-DWG-A-5973
- OTH-PUR-TH-ZZ-DWG-A-5974
- OTH-PUR-TH-ZZ-DWG-A-5975
- OTH-PUR-TH-ZZ-DWG-A-5976
- OTH-PUR-TH-ZZ-DWG-A-5977
- OTH-PUR-TH-ZZ-DWG-A-5978

ISSUE	DATE	APPROVED	DRAWN	DESCRIPTION
07	28/10/2025	RS	JBA	Legend references update to suit new drawings
06	16/08/2024	AD	JBA	Update to Perimeter Boxing following Additional Works PURCELL-EWN-1215
05	06/03/2023	RB	JRC	Perimeter boxing types amended
04	03/01/2023	AB	JRC	Key amended and issued for construction
03	29/10/2021	RB	DW	Issued For Tender
02	06/08/2021	RB	MP	Issued For Tender

OUR TOWN HALL PROJECT

PURCELL

Project Office, Room 308, Town Hall, MANCHESTER M60 2LA
+44 (0) 7970 097 432
www.purcelluk.com

PROJECT STATUS	RIBA STAGE 5
CLIENT	Manchester City Council
PROJECT	OUR TOWN HALL
DRAWING TITLE	Perimeter Boxing Type Location Level LG
SIZE & SCALE	A1: 1 : 200
DRAWING STATUS	FOR CONSTRUCTION
JOB NUMBER	236959
DRAWING NO.	OTH-PUR-TH-LG-DWG-A-0600
REV	07

© PURCELL 2019. PURCELL ® IS THE TRADING NAME OF PURCELL ARCHITECTURE LTD.

28/10/2025 13:35:20