DO NOT SCALE



Legend

Site Boundary

HIGHWAY
40mm SURFACE COURSE
HRA to comply with clause 911 or clause 943.

60mm BINDER COURSE
HRA to comply with clause 905 or 943 or as specified in appendix 7/1.

150mm BASE
Asphalt concrete to comply with clause 906 or 929 or concrete as specified in appendix 7/1.

SUB-BASE - 200mm Granular Sub-Base Material Type 1 to Clause 803 or concrete Grade ST1 to Table 10/1 clause 1001 or as specified in appendix 7/1.
Where sub-grade is silt, clay or made ground, a capping layer or additional sub-base may be required. Capping layer shall be class 6F material to clause 613. If required thickness shall be agreed with the engineer dependant on CBR value of the sub-grade - minimum of 300mm.

FOOTWAY / SERVICE STRIPS
20mm WEARING COURSE
HRA surface to Clause 910 and 911.

40mm BINDER COURSE
Asphalt concrete binder to clause 906 and 929.

100mm SUB-BASE
Type 1 granular material to comply with clause 803

VEHICLE CROSSINGS

20mm Asphalt concrete surface course to clause 909 and 914.

40mm Asphalt concrete binder course to clause 906 and 929

Sub-Base - 150mm Wet lean concrete type ST1 to Clause 1030 in table 10/1.

75mm type 1 granular blinding as required

SHARED ACCESS
Construction materials to suit clients specification

Design based on Layout:
Middleton Road, Crumpsall Site Layout
Rev: P9 (WH-001-NW-A-401 28.08.26)
Grid/Level datum based on Topo:
Middleton Road, Crumpsall. Topographical Survey - 2D
Rev: A

Coopers Drawing List:

8755 / 01	Proposed Drainage Layout
8755 / 02	Proposed Highway Setting Out
8755 / 03	Proposed Highway Layout
8755 / 04	Proposed Highway and Drainage Longsections
8755 / 05	Highway Construction Details
8755 / 06	Proposed Construction Finishes
8755 / 07	S38 Agreement Plan
8755 / 08	External Works Layout
8755 / 09	Private Drainage Layout
8755 / 10	Drainage Construction Details
8755 / 11	Manhole Schedules
8755 / 12	Flow Control Manhole Details
8755 / 13	Manhole Details (if required)
8755 / 14	Surface Water Catchment Areas
8755 / 15	Surface Water Details
8755 / 16	Exceedance Flood Routing Plan
8755 / 17	Setting Out Co-Ordinates
8755 / 18	Vehicle Tracking

TENDER

Rev	Date	Revision	By	Appd.
B	15.09.26	Updated to suit latest planning layout	PW	AJ
A	04.06.26	Existing turning head removed	PW	AJ

coopers
chartered consulting engineers
Park House
Sandpiper Court
Chester Business Park
Chester
CH4 9QU
Tel: 01244 684910
Email: admin@coopers.co.uk
Web: http://coopers.co.uk

Client
WAINHOMES NORTH WEST

Project
Middleton Road,
Crumpsall, Manchester

Title
Proposed Construction Finishes

DRAWING NUMBER
8755 / 06

SCALE at A2 1:500
DATE 27.05.26
DRAWN PW
CHECKED AJ
REVISION B

© Copyright
The original of this drawing contained coloured symbols and/or features.
Any black and white reproduction should not be relied upon.