ARUP

Job No.	Sheet No.	Rev.
298717-00		P01


Member/Location

Job Title: Manchester Art Gallery

Electrical Services - Luminaire Schedule

Made by: HG | Date: 12/08/26 | Chd.: ML

Notes
1. This schedule shall be read in conjunction with all other project drawings and documents.
2. Contractor shall refer to the drawings for final quantities.

Luminaire Family	Luminaire Image	Description	Dimensions (LxWxH) / Ø	Mounting	Rated luminous flux (lumens)	Wattage	Protection Rating	Example Manufacturer	Example Product Ref	Optical Distribution	Light Source Colour	Other
External												
P1		Inground recessed luminaire - Large	Ø275 x 275mm	Floor recessed	1,750	20.0	IP66	Kingfisher	ING260-AB-SY65-840-20-30	80	3000K	Luminaire requires protective housing for water drainage. Ensure minimal glare fixtures. Dimmable driver.
P4		Wedge light for lightwells	220 x 222 x 220mm	Wall mounted	600	12.0	IP65	WE-EF	OLV330	[M] symmetric, medium beam	3000K	RAL9004
A1		Bulkhead for lightwells	220 x 85 x 120mm	Wall mounted	695	5.1	IP67	BEGA	24 355	30	3000K	Anthenaeum lightwell bulkhead
01		Inground recessed luminaire - Small	Ø112 x 134mm	Floor recessed	1,350	12.0	IP66	Kingfisher	ING90-AB-DR-SY80-840-12-30	65	3000K	Luminaire requires protective housing for water drainage. Ensure minimal glare fixtures. Dimmable driver.