342 SLADE LANE, FALLOWFIELD

PROVISIONAL - SUBJECT TO APPROVAL

MANHOLE SCHEDULE

Sheet 1 of 2

Manhole Number / Coordinates	Cover Level / Depth To Soffit	Connections	Pipe: Code	Pipe: Inverts	Pipe: Diams	Manhole Size	Types
F1 E. 461.746 N. 1707.964	48.500 0.750		0	1.000	47.650	100	450	PPIC
F2 E. 448.790 N. 1708.364	48.200 0.750		0	2.000	47.350	100	450	PPIC
F3 E. 460.116 N. 1712.362	48.200 1.051		1 2 0	2.000 1.000 1.001	47.050 47.049 47.049	100 100 100	450	PPIC
F4 E. 456.983 N. 1720.817	48.200 1.180		1 0	1.001 1.002	46.920 46.920	100 100	450	PPIC

MANHOLE SCHEDULE

Sheet 2 of 2

Manhole Number / Coordinates	Cover Level / Depth To Soffit	Connections	Pipe: Code	Pipe: Inverts	Pipe: Diams	Manhole Size	Types
S1 E. 469.809 N. 1704.257	48.500 0.600		0	1.000	47.675	225	260	RE
S2 E. 474.704 N. 1725.104	48.500 0.814		1 0	1.000 1.001	47.461 47.461	225 225	450	PPIC
S3 E. 469.436 N. 1726.241	48.500 0.868		1 0	1.001 1.002	47.407 47.407	225 225	450	PPIC
S4 E. 461.419 N. 1705.912	48.500 0.866		0	2.000	47.409	225	260	RE
S5 E. 456.700 N. 1719.659	48.200 0.711		1 2 0	2.000 1.002 1.003	47.264 47.264 47.264	225 225 225	450	PPIC
S6 E. 442.667 N. 1706.490	48.200 1.067		0	3.000	46.908	225	450	PPIC
S7 E. 440.207 N. 1713.703	48.200 1.118		1 0	3.000 3.001	46.857 46.857	225 225	450	PPIC
S8 Flow Control MH 2.0l/s Max Discharge E. 451.766 N. 1717.911	48.200 1.275		1 2 0	3.001 1.003 1.004	46.775 46.775 46.775	225 225 150	1050	FC
C1 E. 451.201 N. 1719.545	48.451 1.543		1 2 0	SW FW 1.005	46.758 46.808 46.758	150 100 150	450	PPIC

DESIGN NOTE
ALL RWP AND SVP POSITIONS ARE INDICATIVE PLEASE REFER TO THE WORKING DRAWINGS FOR EXACT POSITIONS

DESIGN NOTE
SECTION 106 APPLICATION TO BE IN PLACE WITH UNITED UTILITIES BEFORE CONNECTION IS MADE TO THE PUBLIC SEWER SYSTEM.

DESIGN NOTE
REFER TO THE UTILITY SURVEY FOR POSITION AND DEPTHS OF APPARATUS. POSITION AND LEVEL OF THE OUTFALL DEPENDANT ON DEPTHS OF SERVICES.

Rev	Amendments	Date	Drawn
D	Design updated to LA comments	09.10.26	CML
C	Design updated to LA comments	07.09.26	CML
B	Design updated to LA comments	06.07.26	CML
A	Design updated to new information supplied by client	27.04.26	CML
-	Initial issue	30.03.26	CML

PROVISIONAL - Subject to approval

Client

D Woodman Developments

Project Title

342 SLADE LANE FALLOWFIELD

Drawing Title

PROVISIONAL MANHOLE SCHEDULES

Scales: NTS @ A3

Drawn: CML

Date: 30.03.26

Ref: SL-F-10-02

Rev: D