

SURFACE TREATMENTS

Paving Flags 1
300 x 150/200/300 x 50mm flags - Magma granite appearance. To be laid stretcher bond. Supplied by www.marshscape.co.uk or similar approved manufacturer

Resin Bound Gravel - Winter Pearl
6mm natural aggregate resin bound gravel in winter pearl colour. Supplied by www.sureset.co.uk or similar approved manufacturer

Self Binding Gravel - Cedec or similar

Loose pea gravel

Bitmac

TTI
Paving system with gravel infill. sales@geosyn.co.uk or similar approved

Area of 'Roof bridge' construction

Concrete Blocks
200 x 100 concrete permeable blocks laid in herringbone pattern

EDGES

Corten edging
corten steel edging. Supplied by Kinley sales@kinley.co.uk or similar approved

FEATURES

Backless Bench
Timber Backless Beam Seat Supplied by Woodscape www.woodscape.co.uk or similar approved manufacturer

Corten Steel Planter
Corten steel modular linear planter system 450 mm above ground level. Supplied by Bailey Street Furniture Group www.baileystreetscene.co.uk or similar approved

Timber Pergola Arches
Pressure and fire retardent treated hardwood timber

Boundary Treatments

Timber boundary fence
2100mm high tongue and groove timber fence with 300mm trellis inset

Existing low stone wall repaired and retained as necessary

1.8m high Paladin mesh security fencing

SOFTWORKS

Multistemmed Trees
Native tree species to be planted as 3m high Multi-stemmed specimens.

Proposed Medium/ Large Trees
Native and Trees To be planted as 14-16cm girth Extra Heavy Standards within the development. Trees to be planted and secured in place with double timber stakes, cross bar and tree ties.

Native Trees
Native Trees to be planted as feathered whips 175-250 cm height within the development. Trees to be planted and secured in place with double timber stakes, cross bar and tree ties.

Native scrub understorey
40-80cm Bare root shrubs planted at 1/m2

Fruit Trees
Trees to be planted and secured in place with double timber stakes, cross bar and tree ties.

Proposed Specimen Shrubs
Native and Ornamental shrubs to be planted as 10L pots

Ornamental Shrubs
Raised planters and shrub beds to be planted with a mixture of shrubs in 5L pots at 3 per sq.m, grasses and herbaceous perennials in 1L pots at 5 per sq.m and 25L specimens to be planted in the beds to provide instant height and structure. Beds to be mulched with a small grade bark mulch.

Proposed Wildflower Turf
Areas to be laid with wildflower turf EM1 General purpose meadow mixture. To be regularly maintained.

Native Hedgerow

Amenity grass

DEP LANDSCAPE ARCHITECTURE LTD

2 COMMERCIAL STREET
MANCHESTER, M15 4RQ
T: 0161 2419878
E: info@dep.co.uk
W: www.dep.co.uk

Client
Atzaro Real Estate

Project
Palatine Road

Description
Landscape Proposals

Status
For Planning

Scale
1:200@A1

Drawn
BH

Job number
6008

Drawing number
01

Date
08.09.26

Revision
D

Copyright DEP Landscape Architecture Ltd

All levels and dimensions to be checked on site by contractor prior to commencement; Any variations to be reported to the client. This drawing is to be read in conjunction with all others relating to the project and all information derived accordingly; any anomolies to be reported to the client. Do not scale from this drawing. Use figured dimensions only. Work shown on this drawings to be carried out in accordance with current British Standards and Codes of Practice.

© Copyright to DEP Landscape Architecture Limited. The information shown on this drawing shall not be reproduced or copied in any form without prior written consent from DEP Landscape Architecture Limited.